



DSII 3000 HP Quick Move Elevator Rig Package

Drawworks

Rebuilt Nat'l 1625 UE, 3000 HP, grooved for 1-5/8" drill line with three refurbished G.E. 752 series wound DC traction motors, El Magco Auxiliary Brake, make-up and breakout catheads.

Mast

New DSI 152' x 30' x 1500K Cantilever Mast with crown containing seven (7) main cluster sheaves and one fastline sheave. Mast to include racking board and raising lines

Substructure

New DSII 30' High Winch Raised 1,000,000# casing, 800,000# setback, complete with three sets of stairs, and other accessories

Rig Moving Equipment

1 Set of four point rig moving equipment which is designed to move the substructure complete with drawworks and mast in place

Mud Pumps

Three New Gardner Denver PZ-11, 1600 HP packages each with master skid, six DC traction motors, drive sheaves, belts, belt guards, charge pump, liner wash system, etc.

Mud Pump Moving Equipment

Trailerized mud pump package equipped with required hydraulic jacking system, gooseneck with fifth wheel and sand tires. Minimum ground clearance on level surface to be 24"

Rig Power

New 5x5 SCR System/Control House with 1000 KVA main transformer, 225 KVA lighting transformer and adequate MCC to operate the rig

Five New Caterpillar 3512C diesel engines each with Caterpillar SR4, 1750 KVA generator and radiator, set on a 10' wide x 40' long master skid with roof, muffler, etc.

Two New Gardner Denver 50 HP compressors, one cold start, one air dryer and two 400 gallon volume tanks to be included

Power Trailers

One (1) Power Trailer to Accommodate SCR System, Engine/Generator Skid Packages, HPU, and Rig Air System with interconnecting pipes, hoses, etc. for quick rig up and down

Rotating Equipment

"Rebuilt" 37 1/2" Rotary Table with Independent Hydraulic Drive

New CanRig 750 Ton Top Drive – Model 1275 AC

Mud System

New 3000 BBL., 6-tank round bottom mud system with false roofs, complete with Nineteen 10 HP agitators, two 15 HP agitators, Six 5x6 centrifugal pumps with 100 HP motors

Solid Control Equipment to consisting of:
Three Derrick 503 shakers, One Derrick 1200 gpm Vacuum Degasser, One Derrick 503 Mud Cleaner – 1200 gpm, Two High Shear Mud Hoppers.

Miscellaneous

New Single Porch Driller's Side Doghouse

New Mech. /Warehouse Workshop

New CanRig 750 Ton block

100 BBL Trip Tank/ Choke Manifold/ Mud-Gas Separator Combo Unit

1200 Gallon Closed Loop Brake Water System complete with two centrifugal pumps, plate heat exchanger, and safety alarm package

Hydraulic Power Unit (70 GPM @ 3000 psi capable)

New Accumulator/Junk Bin Skid with New 7 Station Closing Unit.

13-5/8", 10000# Single and Double BOP

13-5/8", 10000# Annular BOP

Two (2) 12,700 Gallon Fuel Tank with transfer pumps

New 500 BBL Water Tank

New Drill Line Spooler with 7500' of 1-5/8" Drill Line

Features:

Rig can be equipped with either a skidding system (Well pattern needed for final pricing).

Substructure transports in three compact loads including One piece center steel with Independent Rotary Drive with NO removable flooring or diagonal braces

Delivery: 120-150 Days

For a full quote contact Nycholas Jaquette at njaquette@drillingstructuresintl.com

www.drillingstructuresintl.com

(281)880-8833